



Union Gas—Ancaster, Ontario

Size: 10'0" wide x 27'0" long x 12'0" high

Series: Durashed

Date of Approval

to Proceed: October 10, 1998

Date of Completion: November 18, 1998

Project Information:

In conjunction with Union Gas Limited, Maritimes & Northeast Pipeline and Viessmann Manufacturing, NRB Modular Building Systems has manufactured several steel frame, exterior, "Boiler" enclosures.

This particular project for the Ancaster Transmission Station, was delivered to the site in one piece and craned into position.

This pre-engineered steel building has an inside height of 12'0". A structural steel floor assembly supports the equipment inside. The wall and roof assembly is fully insulated.

NRB Modular Buildings. Ready when you are.



Door Type 1: Double Door



Door Type 2: Overhead Door