

## **Inova Fair Oaks Hospital Fairfax, Virginia**

**Size:** 26'0" x 61'0"

**Date of Production Start:** Jan. 17, 2002

**Ship Date:** March 21, 2002



### **Project Information**

This extremely busy hospital needed an addition, but couldn't accommodate or tolerate the huge disruption that site construction would have caused.

In just 45 days, this 1586 square foot addition was built off site by NRB using a steel framed post and beam construction. The concrete floor was even pre-poured at the plant. The three steel framed building modules were then assembled on site. The brick exterior was installed on site in order to perfectly match the existing hospital's façade.



*Another quality facility built by NRB for Modular Solutions, LLC, Carmel, IN*

**NRB Modular Buildings. Ready when you are.**